

CONTRACTOR MUST PROVIDE SHOP  
DRAWING DETAIL OF COVERED WALKWAY  
FOR REVIEW AND APPROVAL TO THE  
TRAFFIC OPERATIONS SECTION, IF  
ALTERNATE MATERIALS FOR WALKWAY  
ARE PROPOSED

1/2" MIN. THICK PLYWOOD  
2" THICK ROOF DECK

2" X 8" FULL LENGTH  
ONE ON EACH SIDE

SLOPE DOWN TOWARDS CURBLINE  
ROLLED ROOFING

2" X 8" ON 4' O/C

WIRE MESH OR  
1/2" PLYWOOD

2" X 4" TYP.  
EACH STUD

40 WATT LIGHT  
W/ GUARD  
ON 16' FT O/C

BACK SIDE  
(WORK AREA)

FRONT SIDE  
(ROAD SIDE)

6" LAP

4" X 4" ON 2' O/C

1/2" PLYWOOD  
6' 0" HIGH MIN.

2" X 4"  
HANDRAIL

8' CLEAR

WIRE MESH, CONTINUOUS

3'6"

5/8" PLYWOOD  
FLOOR

5 FT MIN.

4" X 4" ON 2' O/C

PROVIDE TEMPORARY ASPHALT WEDGE  
FROM CURB TO EXISTING  
PAVING AS NECESSARY

DATE	TRAFFIC OPERATIONS SECTION		
07-01-04	MONTGOMERY COUNTY, MARYLAND		
DES. BY			
MCDPWT	COVERED WALKWAY		
DRAWN BY	APPROVED		
TCLE			
SCALE	CHIEF, TRAFFIC OPERATIONS SECTION		
NTS	STANDARD TCP-107.03 OF SHEETS		

REVISION BY	DATE	APPROVED